

**DISTRICT MUNICIPAL CORPORATION (KORANGI) KARACHI.**  
**SHAH FAISAL ZONE.**

Estimate Cost: Rs: 9, 96,889/-  
2% Earnest Money: 2 % Quoted Amount  
Tender Cost: Rs: 3,000/-  
Penalty Per day: Rs: 3,000/-  
Time Limit: 01 Month

S. No. 02

**Subject: Improvement of Boundary wall in Azam Foot Ball Ground in UC,, No-1 Shah Faisal Zone D.M.C Korangi.**

S.NO.	DESCRIPTION OF WORK	Quantity	RATE	AMOUNT
1.	Earth work excavation in foundation of buildings.	7160 Cft	1361.25 % cft	9,747/-
2.	Cement concrete brick on stone ballast 1.5 to 2" gauge 1;4;8.	2350 cft	9416.28 % cft	2,21,283/-
3.	Reinforcement Cement concrete work i/c all labor (a) RCC work in roof slab, beam column rafts and other structure members laid in situ or pre cast laid in position complete in all respect. (i) Ratio 1;2;4	863 cft	337/- P/cft	2,90,831/-
4.	Fabrication of Mild steel re enforcement for cement concrete i/c cutting, bending, laying in position, making joints & fasting i/c cost of binding wire etc.	38.52 cwt	5001.70 P/cwt	1,92,666/-
5.	Providing and laying topping cement concrete (1:2:4) including surface finishing and dividing into panel 2" thick.	2000 Sft	3275.50 % sft	65,510/-
6.	Providing & laying 1:3:6 cement concrete solid block masonry wall 6" and below in thickness set in 1.6 cement sand mortar in ground floor super structure including raking out joints and curing etc. complete more than 6" think (22/23)	1375 Cft	15771.08 % cft	2,16,852/-

I/We hereby quoted the Total Amount for items on Open Rate Rs: \_\_\_\_\_

And also shall undertake to abide by prescribed terms and condition of the Contractor.

\_\_\_\_\_  
Contractor Signature

Address \_\_\_\_\_

Deputy Director (Parks)  
Shah Faisal Zone D.M.C Korangi

Sr. Director (Parks)  
D.M.C Korangi

**DISTRICT MUNICIPAL CORPORATION (KORANGI) KARACHI.**  
**SHAH FAISAL ZONE.**

Estimate Cost: Rs: 9,96,830/-  
2% Earnest Money: 2 % Quoted Amount  
Tender Cost: Rs: 3,000/-  
Penalty Per day: Rs: 3,000/-  
Time Limit: 01 Month

S. No. 01

**Subject: Repair/Maintenance of Different Parks in Uc, No-1 Shah Faisal Zone D.M.C Korangi.**

S.NO.	DESCRIPTION OF WORK	Quantity	RATE	AMOUNT
1.	Dismantling cement Block masonry etc.	125 Cft	1134.38 % cft	1,418/-
2.	Dismantling & Removal of CC 1;3;6	480 Cft	1306.80 % cft	6,273/-
3.	Earth work excavation in foundation of buildings.	2200 Cft	1361.25 % cft	2,995/-
4.	Cement concrete brick on stone ballast 1.5 to 2" gauge 1;4;8.	1300 cft	9416.28 % cft	1,22,412/-
5.	Cement concrete plain including placing compacting finishing and curing complete (including searching and washing of stone Aggregate) without shuttering. (18/5) Ratio 1:2:4	1050 Cft	14429.25 % cft	1,51,507/-
6.	Exaction of removal of centering of RCC for plain cement concurrent work of portal wood vertical.	2100 Sft	3127.41 % sft	65,676/-
7.	Reinforcement Cement concrete work i/c all labor (a) RCC work in roof slab, beam column rafts and other structure members laid in situ or pre cast laid in position complete in all respect. (i) Ratio 1;2;4	216 cft	337/- P/cft	72,792/-
8.	Fabrication of Mild steel re enforcement for cement concrete i/c cutting, bending, laying in position, making joints & fasting i/c cost of binding wire etc.	7.71 cwt	5001.70 P/cwt	38,563/-
9.	Providing and laying topping cement concrete (1:2:4) including surface finishing and dividing into panel 2" thick.	4000 Sft	3275.50 % sft	1,31,020/-
10.	Cement plasters 1:4 up to 20 feet height. (53/11) ½" thick	1460 Sft	2283.93 % sft	33,345/-
11.	Painting with enamel paint on masonry (plastered) tow coats (Old Surface).	600 Sft	1014.14 % Sft	6,085/-
12.	Distempering two coats with distemper of app; quality and shade, i/c priming coat. (Old surface)	2600 sft	602.25 % Sft	15,659/-
13.	S/S approved sweet earth (Garden Soil) free from salts, pebbles, suitable for plants brought from app: query near Noori Abad, i/c loading, carriage, un-			


	loading at site of work and spreading in even layer of req: thickness to proper level as required/ directed by concerned Officer in charge.	2640 Cft	35/- A/R P/Cft	92,400/-
14.	S/S and spreading appr: well decayed cow dung i/c mixing in earth, laying spreading in even layers of req: thickness as required/ directed by concerned Officer in charge.	2300 Cft	30/- A/R P/Cft	69,000/-
15.	Providing of Dhaka grass and trufing lawns i/c watering and cutting at least once after growing up more then 3 inches.	1554 sft	15/- A/R P/Cft	23,310/-
16.	Providing supplying and spreading in even layer of required thickness red murum of approved quality from app; query as desired by Engineer In charge	1875 Cft	45/- A/R P/Cft	84,375/-
17.	Repair/Maintenance of Steel grill using solid aqr, bars of size ½" thick i/c welding & fixing of door/window any type 2 coats painting & direction of Engineer In charge etc.	800 sft	100/- A/R P/Cft	80,000/-


I/We hereby quoted the Total Amount for items on Open Rate Rs: \_\_\_\_\_

And also shall undertake to abide by prescribed terms and condition of the Contractor.

\_\_\_\_\_  
Contractor Signature

\_\_\_\_\_  
Address

  
\_\_\_\_\_  
Deputy Director (Parks)  
Shah Faisal Zone D.M.C Korangi

  
\_\_\_\_\_  
Sr. Director (Parks)  
D.M.C Korangi

# DISTRICT MUNICIPAL CORPORATION KORANGI KARACHI.

## SHAH FAISAL ZONE

Estimate cost: 9,99,168/-  
 2% Earnest money: 2% Quoted Amount  
 Tender Cost : Rs. 3000/-  
 Penalty Per Day: Rs. 3000/-  
 Time limit: 01 month

S.no.03

**Subject : Repair / Maintenance of different parks in Uc no 2 Shah faisal Zone DMC Korangi**

S.no	Description of Work	Quantity	Rate	Amount
1	Dismantling cement block masonry etc.	125	1134.38% cft	1418/-
2	Earth work excavation in foundation of buildings	2200	1361.25% cft	2995/-
3	Cement concrete brick on stone ballast 1.5 to 2" gauge 1:4:8	1300	9416.28% cft	122412/-
4	Cement concrete plain including placing compacting finishing and curing complete (including searching and washing of stone aggregate) without shuttering. (18/5) Ratio 1:2:4	1050	14429.25% cft	151507/-
5	Erection & removal of centering of RCC for plain cement concurrent work of portal wood vertical	2100	3127.41% sft	65676/-
9	Providing and laying topping cement concrete 1;2;4 including surface finishing and dividing into panel 2" thick.	4000	3275.50% sft	131020/-
10	Cement plasters 1:4 upto 20 feet height. ½ thick	1460	2283.93 % sft	33345/-
	Painting guard bars, gates, iron bars, gratings, i/c braces and similar open work. (76/4d) 2 coats		896.39% sft	
11	Painting with enamel paint on masonry plastered two coats old surface	600	1014.14% sft	6085/-
12	Disterpering two coats with distemper of app: quality and shade, i/c priming coat.	2600	602.25% Sft	15659/-
6	P/Fixing Industrially manufactured kurb block of size 18x12x6 having Strength of 4700 psi, fixed in proper alignment and lavel on 2" thick base of 1:4	130.0	297.01 /R4	38611/-
7	Reinforcement cement concrete work I/C All lab our (a) RCC Work in roof slab beam column rafts and other structure members laid in situ precast laid in position completed in all respect (i) Ratio 1,2,4	216.00	337/CFT	72792
13	S/S Approved Sweet earth (Garden Soli) Free From Salts ,Pebbles ,Suitable For Plants Brought From App: query near noori Abad i/c loading Carriage ,un loading at side of work and spreading in even layer of rec : thickness to proper level as required /directed by concerned Officer in Charge	2640.00	35/CFT	92400/-
14	S/S and Spreading Appr: Well Decayed cowdung i/c mixing in earth , laying Spreading in even layers of req : thickness as required /directed by concerned Officer in Charge	2300.00	30/CFT	69000/-

15	Providing of Dhaka grass and turfing lawns i/c watering and cutting at least once after growing up more than 3 inches	1554.00	15/SFT	23310/-
16	Providing supplying and spreading in even layer of required thickness, murum of approved quality from app : query as desired by engineer in charge.	1875	45 cft	84375/-
8	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making joints 7 fasting i/c cast of binding wire etc.	7.71	5001.7 cft	38563/-
17	Repair maintenance of steel grill using solid square bars of size ½ & ¾ thick i/c welding 4 fixing of door / window any type 2 coats painting etc .	500	100/ sft A/R	50000/-

I / we hereby quoted the total amount for items on open rate

Rs: \_\_\_\_\_

And also shall undertake to abide by prescribed terms and condition of the Contractor.

\_\_\_\_\_  
Contractor Signature

Address \_\_\_\_\_



Deputy Director Parks  
Shah Faisal Zone DMC Korangi



Sr. Director Park  
DMC Korangi