

Name of work: M/R to Secretary Bungalow No.7 Town Houses GOR III Karachi (Electric Work)

Schedule B

S.No.	Description	Qty	Rate	Unit	Amount
1	Wiring for light or fan point with 3/029 PVC insulated wire in 20mm (3/4)channel patti on surface as required.(S.I.129/15)	23-Nos	910/-	Each	20930
2	Wiring for Plug point with 3/029 PVC insulated wire in 20mm (3/4)channel patti on surface as required.(S.I.130/15)	6-Nos	742/-	Each	4452
3	Wiring for Call bell point with 3/029 PVC insulated wire in 20mm (3/4)channel patti on surface as required.(S.I.131/15)	1-No	1590/-	Each	1590
4	P/L main or Sub main PVC insulated with size 2-7/044 (4mm ²) copper conductor in 3/4" dia PVC conduit on surface.(S.I.14/1)	60.00 Meter	305/-	p.Meter	18300
5	P/L main or Sub main PVC insulated with size 2-7/036 (4mm ²) copper conductor in 3/4" dia PVC conduit on surface.(S.I.14/1)	50.00 Meter	200/-	p.Meter	10000
6	P/F Circuit Brackers 6,10,15,20, 30,40,50 & 63 amps SP (TB SS) on a prepared board as required.(S.I.203/31)	15-Nos	916/-	Each	13740
7	P/F circuit bracker 15,20,30 40,50,60,75.&100 amp TP EX(100)CS (CB) on Prepared board as required.(S.I.207/31)	2-Nos	9261/-	Each	18522
8	P/F one way SP for 10/15 amps switch surface type (S.I.22/218/33)	50-Nos	58/-	Each	2900
9	P/F two way Pin 5-amps Plug & socket flush type (S.I.23/225/33)	15-Nos	83/-	Each	1245
10	P/F Brass Batten Holder (S.I.232/33/232)	25-Nos	70/-	"	1750
	Total				93429
	Part B N.S.I				
1	P/F Power Plug 15-Amps imported quality i/c board etc complete.	12-Nos		Each	
2	P/F Universal 5-10 amps imported quality i/c board etc complete.	10-Nos		"	
3	P/F Fancy Wall Light i/c shade holder i/c necessary electric connection etc complete.	26-Nos		"	
4	P/F Ceiling Light with holder i/c electric connection etc complete.	14-Nos		"	
5	P/F Exhaust Fan Plastic Body equelent quality i/c necessary electric connection as per approved quality etc complete.	6-Nos		Each	
6	P/F Ceiling Fan 56" Sweep make Pak or equelent quality i/c necessary electric connection etc complete.	12-Nos		"	
7	P/F Energy Saver 25 watt i/c holder as per approved quality i/c necessary electric connection etc complete.	40-Nos		"	

CHECKED

8	P/F Mirror Light with holder i/c electric connection etc complete.	5-Nos ✓		"	
9	P/F Gate Light with holder i/c electric connection etc complete.	2-Nos ✓		"	
10	P/F Tube Light 40 watt fancy type i/c chock rod patti starter etc complete.	6-Nos ✓		"	
	Total B				
	G Total				

TERMS & CONDITION

1. Any typographical errors in the schedule B are subject to the correct condition with Reference to the schedule of rate General 2012 enforced from 12-07-2012 as approved by the SRC Sindh.
2. Arbitration clause stands deleted from the agreement.
3. No Premium shall be paid on Non Schedule Items
4. 100% well Graded crushed bajri shall be used in items of work without any extra payment.
5. No any items of exveceed then the quantity provided in the schedule B without prior of the Executive Engineer.
6. All sample of items should be got approved by the Executive Engineer.

Contractor


 Assistant Engineer,
 Electrical Sub Division-XII,
 Karachi