

BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

OF WORK:- Provision of Missing Facilities under Education Sector Reforms (ESR) (2009-10 Programme)
**PACKAGE-II (i) GBPS Habibullah Mungrani Tal: G.Yasin (ii) GBPS Muhammad Saleh Chachar @
Jumo Jhangwani Taluka Khanpur**

| Item | Quantities | Description of item to be executed at site | Rate | Units | Amount |
|------|------------|---|----------|-----------------|---------------|
| | | <u>PART-A SCHEDULE ITEM</u> | | | |
| 1 | 20 | Wiring for light or fan point with (3/029) PVC insulated wire in 20 mm(3/4") Chennal pati on surface as required (S.I.NO. 129 .P.NO.15) | 910.00 | P.Point | 18,200 |
| 2 | 4 | Wiring for plug with (3/0.29(PVC insulated wire in 20mm (3/4") | 742.00 | P.Point | 2,968 |
| 3 | 70 | Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-7/0.29 coper conductor on surface fitted (S.I.NO.3.P.NO.33) | 171.00 | P.Meet: | 11,970 |
| 4 | 20 | Providing and Fixing One Way S.P.5 amps switch flush type (S.I.NO.219.P.NO.33) | 54.00 | P.No: | 1,080 |
| 5 | 4 | Providing and Fixing Two Pin S.P.5 amps Plug & Socket (S.I.NO.225.P.NO.33) | 83.00 | P.No: | 332 |
| 6 | 1 | Providing and Fixing Three Pin 10/15 amps Plug & Socket Flush type (S.I.NO.226.P.NO.33) | 151.00 | P.No: | 151 |
| 7 | 6 | Providing and Fixing Circuit Breker 6,10,15,20,30,40,50 & 63 amps S.P (TB-5S) on prapired board as required (S.I.NO.202.P.NO.30) | 916.00 | P.No: | 5,496 |
| 8 | 2 | Providing and Fixing Circuit Breker 6,10,15,20,30,40,50 & 63 amps D.P (TB-5S) on prapired board as required (S.I.NO.202.P.NO.30) | 2,456.00 | P.No: | 4,912 |
| 9 | 6 | Providing and Fixing Bake lite ceiling rose with two terminels (S.I.NO.228.P.NO.33) | 72.00 | P.No: | 432 |
| 10 | 10 | Providing and Fixing Brass Button holder (S.I.NO.232.P.NO.33) | 70.00 | P.No: | 700 |
| 11 | 6 | Providing and Fixing ceiling fans 56" size good qulity (S.I.NO.235.P.NO.34) | 3,185.00 | P.No: | 19,110 |
| 12 | 40 | Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-7/0.52 (10mm 2)coper conductor in 1" dia PVC conduate | 428.00 | P.No: | 17,120 |
| | | | | Total -A | 82,471 |

| | | | | | |
|----|---|---|----------|-------|-------|
| | | <u>PART-B NON SCHEDULE ITEMS 2004</u> | | | |
| 1 | 2 | Providing and Fixing distribution matel board dobbble shuter to accomodate circuit breakers i/cpainting with enemal pail and for other similer job on surface (S.I.NO.18.P.NO.13) | 907.96 | P.Sft | 1,816 |
| 2 | 6 | Providing and Fixing miled steel bar fan clamps 15.8 mm (5/8") dia suitable for R.C.C (S.I.NO.1.P.NO.14) | 141.01 | P.No: | 846 |
| 3 | 0 | Providing and Fixing 1-40 watts tubelights copmlete with 40 watts 4" long etc complete (S.I.NO.1.P.NO.33) | 396.00 | P.No: | - |
| 4 | 4 | Providing and Fixing wall brakate light fancy type superior quality i/c necessary connection and fixing on wall or ceiling ect complete (S.I.NO.5.P.NO.33) | 497.00 | P.No: | 1,988 |
| 5 | 6 | Providing and Fixing energy sawer superior quality i/c fixing on existing holder etc complete (S.I.NO.6.P.NO.33) | 497.00 | P.No: | 2,982 |
| 6 | 4 | Providing and Fixing Blub 100 watt (S.I.NO. .P.NO.) | 25.00 | P.No: | 100 |
| 7 | 6 | Providing and Fixing A.C ciling fans regulator on matel board recessed in the walls columns and cover with plastic sheet (S.I.NO.2b.P.NO.14) | 124.30 | P.No: | 746 |
| 10 | 2 | Providing & fixing earthin set with 2x2x1/4" cooper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal, etc i/c making the pit 12" deep by excavation of all type of soil Earth plat to be connec | 3,610.04 | P.No: | 7,220 |