

BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

NAME OF WORK:-

Construction of 2-Roomed Shelterless Primary Schools in Sindh (2007-08 Programme)
PACKAGE-VII (i) GBPS Allah Warayo Jafferri (ii) GBPS Azeem Jafferri Tal: Khanpur

| Item No. | Quantities | Description of item to be executed at site | Rate | Units | Amount |
|------------------------------------|------------|--|----------|-----------------|----------------|
| <u>PART-A SCHEDULE ITEM</u> | | | | | |
| 1 | 40 | Wiring for light or fan point with (3/029) PVC insulated wire in 20 mm(3/4") Chennal pati on surface as required | 910.00 | P.Point | 36,400 |
| 2 | 8 | Wiring for plug with (3/0.29(PVC insulated wire in 20mm (3/4") Chennal pati on surface as required | 742.00 | P.Point | 5,936 |
| 3 | 170 | Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-7/0.29 coper conductor on surface | 171.00 | P.Meet: | 29,070 |
| 4 | 40 | Providing and Fixing One Way S.P.5 amps switch flush type (S.I.NO.219.P.NO.33) | 54.00 | P.No: | 2,160 |
| 5 | 8 | Providing and Fixing Two Pin S.P.5 amps Plug & Socket (S.I.NO.225.P.NO.33) | 83.00 | P.No: | 664 |
| 6 | 2 | Providing and Fixing Three Pin 10/15 amps Plug & Socket Flush type (S.I.NO.226.P.NO.33) | 151.00 | P.No: | 302 |
| 7 | 12 | Providing and Fixing Circuit Breker 6,10,15,20,30,40,50 & 63 amps S.P (TB-5S) on prapired board as required | 916.00 | P.No: | 10,992 |
| 8 | 2 | Providing and Fixing Circuit Breker 6,10,15,20,30,40,50 & 63 amps D.P (TB-5S) on prapired board as required | 2,456.00 | P.No: | 4,912 |
| 9 | 12 | Providing and Fixing Bake lite ceiling rose with two terminels (S.I.NO.228.P.NO.33) | 72.00 | P.No: | 864 |
| 10 | 20 | Providing and Fixing Brass Button holder (S.I.NO.232.P.NO.33) | 70.00 | P.No: | 1,400 |
| 11 | 12 | Providing and Fixing ceiling fans 56" size good qulity (S.I.NO.235.P.NO.34) | 3,185.00 | P.No: | 38,220 |
| 12 | 100 | Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-7/0.52 (10mm 2)coper conductor in | 428.00 | P.No: | 42,800 |
| | | | | Total -A | 173,720 |

| | | | | | |
|--|----|---|--------|-------|-------|
| <u>PART-B NON SCHEDULE ITEMS 2004</u> | | | | | |
| 1 | 2 | Providing and Fixing distribution matel board dobbble shuter to accommodate circuit brekers i/cpainting with enemal pail and for other similer job on surface | 907.96 | P.Sft | 1,816 |
| 2 | 6 | Providing and Fixing miled steel bar fan clamps 15.8 mm (5/8") dia suitable for R.C.C (S.I.NO.1.P.NO.14) | 141.01 | P.No: | 846 |
| 3 | 0 | Providing and Fixing 1-40 watts tubelights copmlete with 40 watts 4" long etc complete (S.I.NO.1.P.NO.33) | 396.00 | P.No: | - |
| 4 | 8 | Providing and Fixing wall brakate light fancy type superior quality i/c necessary connection and fixing on wall or ceiling ect complete (S.I.NO.5.P.NO.33) | 497.00 | P.No: | 3,976 |
| 5 | 16 | Providing and Fixing energy sawer superior quality i/c fixing on existing holder etc complete (S.I.NO.6.P.NO.33) | 497.00 | P.No: | 7,952 |
| 6 | 4 | Providing and Fixing Blub 100 watt (S.I.NO. .P.NO.) | 25.00 | P.No: | 100 |
| 7 | 6 | Providing and Fixing A.C ciling fans regulator on matel board recessed in the walls columns and cover with plastic sheet (S.I.NO.2b.P.NO.14) | 124.30 | P.No: | 746 |