

BILL OF QUANTITIES

Discription and Rate of Items based on Composite Schedule of Rates

OF WORK:- Construction / Re-Construction of Existing Offices for field Officers of Education & Literacy Department in Larkana Division

No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
		<u>PART-A SCHEDULE ITEM</u>			
1	84	Wiring for light or fan point with (3/029) PVC insulated wire in 20 mm(3/4") Chennal pati on surface as required (S.I.NO. 129 .P.NO.15)	910.00	P.Point	76,440
2	25	Wiring for plug with (3/0.29(PVC insulated wire in 20mm (3/4") Chennal pati on surface as required (S.I.NO. 130 .P.NO.15)	742.00	P.Point	18,550
3	200	Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-7/0.29 coper conductor on surface fitted (S.I.NO.3.P.NO.33)	171.00	P.Meet:	34,200
4	84	Providing and Fixing One Way S.P.5 amps switch flush type (S.I.NO.219.P.NO.33)	54.00	P.No:	4,536
5	25	Providing and Fixing Two Pin S.P.5 amps Plug & Socket (S.I.NO.225.P.NO.33)	83.00	P.No:	2,075
6	12	Providing and Fixing Three Pin 10/15 amps Plug & Socket Flush type (S.I.NO.226.P.NO.33)	151.00	P.No:	1,812
7	28	Providing and Fixing Circuit Breker 6,10,15,20,30,40,50 & 63 amps S.P (TB-5S) on prapired board as required (S.I.NO.202.P.NO.30)	916.00	P.No:	25,648
8	3	Providing and Fixing Circuit Breker 6,10,15,20,30,40,50 & 63 amps D.P (TB-5S) on prapired board as required (S.I.NO.202.P.NO.30)	2,456.00	P.No:	7,368
9	43	Providing and Fixing Bake lite ceiling rose with two terminels (S.I.NO.228.P.NO.33)	72.00	P.No:	3,096
10	29	Providing and Fixing Brass Button holder (S.I.NO.232.P.NO.33)	70.00	P.No:	2,030
11	21	Providing and Fixing ceiling fans 56" size good qulity (S.I.NO.235.P.NO.34)	3,185.00	P.No:	66,885
12	70	Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-7/0.52 (10mm 2)coper conductor in 1" dia PVC conduate (S.I.NO.6.P.NO.1)	428.00	P.No:	29,960
13	7	Wiring for call bell point with (3/029) PVC insulated wire in 20 mm(3/4") Chennal pati on surface as required	1,590.00	P.Point	11,130
14	20	Wiring for plug with (3/0.29(PVC insulated wire in 20mm (3/4") Chennal pati on surface as required (S.I.NO. 130 .P.NO.15)	742.00	P.Point	14,840
15	100	Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-7/0.36 coper conductor on surface fitted	200.00	P.Meet:	20,000
16	70	Providing & laying (MAIN OR SUB MAIN) PVC insulated with size 2-7/0.44 coper conductor on surface fitted	305.00	P.Meet:	21,350
17	1	Providing and Fixing Circuit Breker 30, 63 & 100 amps T.P (TB-5S) on prapired board as required	9,262.00	P.No:	9,262
				Total -A	349,182
		<u>PART-B NON SCHEDULE ITEMS 2004</u>			
1	4.5	Providing and Fixing distribution matel board dobbble shuter to accomodate circuit brekers i/cpainting with enemal pail and for other similer job on surface (S.I.NO.18.P.NO.13)	907.96	P.Sft	4,086
2	21	Providing and Fixing miled steel bar fan clamps 15.8 mm (5/8") dia suitable for R.C.C (S.I.NO.1.P.NO.14)	141.01	P.No:	2,961
3	19	Providing and Fixing 1-40 watts tubelights copmlete with 40 watts 4" long etc complete (S.I.NO.1.P.NO.33)	396.00	P.No:	7,524
4	12	Providing and Fixing wall brakate light fancy type superior quality i/c necessary connection and fixing on wall or ceiling ect complete (S.I.NO.5.P.NO.33)	497.00	P.No:	5,964
5	26	Providing and Fixing energy sawer superior quality i/c fixing on existing holder etc complete (S.I.NO.6.P.NO.33)	497.00	P.No:	12,922