

B.O.Q OF CIVIL WORK

NAME OF WORK: **REHABILITATION OF EXISTING BUILDING FOR BOYS/GIRLS, PRIMARY/ ELEMENTARY SCHOOLS IN TALUKA KHANPUR DISTRICT SHIKARPUR (2013-14-PROGRAMM) AT G:B:P:S: QAZI PATTI TALUKA KHANPUR DISTRICT SHIKARPUR.**

Sr.No:	QNTY:	DESCRIPTION	RATE	UNIT	AMOUNT IN Rs:
1.	48	Dismantling brick work in lime or cement mortar	@ Rs:1285.63	% Cft	617/-
2.	-	Dismantling brick or flagged flooring without concrete foundation. S.I No.30 P.No.12	@ Rs:257.13	% Sft	-
3.	384	Dismantling cement concrete Plain (1:2:4)	@ Rs:3327.50	% Cft	12778/-
4.	56	Dismantling Cement concrete Reinforced separating reinforcement from concrete cleaning & straightening The same	@ Rs:5445.0	% Cft	3049/-
5.	1411	Dismantling second class tiles roofing	@ Rs:378.13	% Sft	5335/-
6.	-	Removing doors with chowkats	@ Rs:S142.18	P.No:	-
7.	-	Removing windows and sky light with chowkats	@ Rs:102.85	P.No:	-
8.	-	Removing ventilators and wooden sun shade etc.	@ Rs:51.43	P.No.	-
9.	14.439	Dismantling rolled steel beams, iron Rails etc.	@ Rs:126.04	P.Cwt	1820/-
10.	2321	Removing cement or lime plaster	@ Rs:121.00	%Sft	2808/-
11.	-	Dismantling cement concrete plain 1:3:6	@ Rs:1306.80	% Cft	-
12.	181	Excavation in foundation of building bridges and other structure I/C degbelling dressing refilling around the structure with excavated earth watering and ramming lead upto 5 ft. in ordinary soil.	@ Rs:3176.25	%0 Cft	575/-
13.	262	Cement concrete brick or stone ballast 1- 1/2 " to 2" guage i. Cement concrete (ratio 1: 5: 10:) ii. Cement concrete 1: 4: 8:	@ Rs:8694.95 @ Rs:9416.28	% Cft % Cft	22781/-
14.	-	Dry rammed brick or stone ballast 1/2 " thick to 2" guage	@ Rs:3327.50	% Cft	-
15.	80	Pacca brick work in foundation and plinth (cement sand mortar 1:6)	@ Rs:11948.36	% Cft	9559/-
16.	4.576	Fabrication of miled steel reim force ment for cement concrit I/C cutting, banding and lying in position i/c cost of steel binding wire also i/c removal of rust from bars (a) Tor Steel (b) Miled Steel	@ Ps:5001.70 @ Rs:4820.20	P: Cwt P: Cwt	22888/-
17.	102.50	R:C:C: work in roof slab beams columns rafts lintels and other structural members laid in sattu or precast laid in position complete in all respects C:C ratio (1: 2: 4:) S.I No.6A P.No.16	@ Rs:337.00	P: Cft.	34543/-
18.	-	Filling watering ramming earth in floor with surplus earth excavated from foundation lead upto one chain and lift upto 5ft.	@ Rs:1512.50	%0 Cft.	-
19.	450	Filling watering ramming earth under floor with new earth (excavated from outside) lead upto one chain and lift upto five ft.	@ Rs:8655.20	%0 C.ft	3895/-
20.	-	Supplying and filling sand under floor and plugging in wells.	@ Rs:1643.77	% C.ft	-

Contd.....P/2